

2-1-80 - Operations suspended

**FILE NOTATIONS**

Entered in NED File .....  
Location Map Pinned .....  
and Indexed .....

Checked by Chief .....  
Approval Letter .....  
Disapproval Letter .....

**COMPLETION DATA:**

..... 2-1-80

Location Inspected .....

SW..... OS..... RA.....

State or Fee Land ....

**LOGS FILED**

Driller's Log.....

Electric Logs (No.) .....

E..... I..... Deal I Lat..... GR-N..... Micro.....

WC Sonic GR..... Lat..... MI-L..... Sonic.....

... CTOS..... Others .....

**BOWERS OIL & GAS EXPLORATION INC.**

P.O. Box 636

GRAND JUNCTION, CO. 81501

BUS: 303-246-1342

RES: 303-242-6311



April 25, 1979

United States Geological Survey  
8440 Federal Building  
125 S. State Street  
Salt Lake City, Utah 84138

Attention: Mr. E. W. Guynn

RE: Bowers Federal Well #1-34,  
Sec. 34, T19S, R23E, SLB&M,  
Grand County, Utah.

Dear Mr. Guynn:

Enclosed in triplicate is an APD for the captioned well.

Very truly yours,

James E. Bowers  
President

Enclosure  
JEB/bz

CC: Utah Oil and Gas Commission

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

## APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

## 1a. TYPE OF WORK

DRILL ☒DEEPEN ☐PLUG BACK ☐

## b. TYPE OF WELL

OIL  
WELL ☐GAS  
WELL ☒

OTHER

SINGLE  
ZONE ☐MULTIPLE  
ZONE ☐

## 2. NAME OF OPERATOR

Bowers Oil and Gas Exploration, Inc.

## 3. ADDRESS OF OPERATOR

P.O. Box 636, Grand Junction, Colorado 81501

## 4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)\*

At surface

At proposed prod. zone

SAME

## 14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE\*

Approx. 10 miles north by northwest of Cisco, Utah

## 15. DISTANCE FROM PROPOSED\*

LOCATION TO NEAREST

PROPERTY OR LEASE LINE, FT.

(Also to nearest drg. unit line, if any)

367ft.

## 18. DISTANCE FROM PROPOSED LOCATION\*

TO NEAREST WELL, DRILLING, COMPLETED,

OR APPLIED FOR, ON THIS LEASE, FT.

more than 2640ft.

## 16. NO. OF ACRES IN LEASE

2240

## 19. PROPOSED DEPTH

2550'

Morrison

17. NO. OF ACRES ASSIGNED  
TO THIS WELL

160

## 20. ROTARY OR CABLE TOOLS

Rotary

## 21. ELEVATIONS (Show whether DF, RT, GR, etc.)

4965 GR

## 22. APPROX. DATE WORK WILL START\*

1 June, 1979

## 23.

## PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
8 3/4"	7"	20 lb.	200'	60 sx. Class G; 3% CaCl
6 1/4"	4 1/2"	9.5 lb.	2600'	60 sx. RFC, 10-2

SEE ATTACHED PAPER

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

## 24.

SIGNED

A. W. S. Bowers

TITLE President

DATE

4/25/79

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE


APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

\*See Instructions On Reverse Side



SCALE: 1" = 1000'

BOWERS FEDERAL WELL #1-34

Located North 367 feet from the South boundary and West 735 feet from the East boundary of Section 34, T19S, R23E, SLB&M.

Elev. 4965

Grand County, Utah



SURVEYOR'S CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF

*Udell S. Williams*  
UTAH R.L.S. NO. 2573




UDELL S. WILLIAMS  
751 Rood Avenue  
GRAND JUNCTION, COLORADO 81501

PLAT OF  
PROPOSED LOCATION  
BOWERS FEDERAL WELL #1-34  
SE 1/4 SE 1/4 SECTION 34  
T19S, R23E, SLB&M

SURVEYED BY: USW DATE: 5/14/79

DRAWN BY: USW DATE: 5/14/79

# CUT/FILL DIAGRAM FOR WELL #1-34




DRILL PAD - SCALE 1" = 50'

CUT/FILL SECTIONS NOT DRAWN TO SCALE


EAST/WEST CROSS SECTION

# DRILL PAD LAYOUT FOR BOWERS FEDERAL WELL #1-34

N



PROPOSED PRODUCTION FACILITIES FOR BOWERS FED. WELL #1-34



STATE OF UTAH  
DIVISION OF OIL, GAS, AND MINING

\*\* FILE NOTATIONS \*\*

Date: May 21, 1979

Operator: Bowers Oil & Gas Exploration, Inc.

Well No: Bowers Federal 1-34

Location: Sec. 34 T. 19S R. 23E County: Grand

File Prepared: ☐

Entered on N.I.D.: ☒

Card Indexed: ☒

Completion Sheet: ☒

API Number: 43-019-30573

CHECKED BY:

Administrative Assistant: \_\_\_\_\_

Remarks:

Petroleum Engineer: M. J. Minder 11-8-79

Remarks: Unorthodox location Called 5-25-79 Jim Bowers will change location - Called J. Bowers 10-1-79 he will change location to fit 102-16

Director: \_\_\_\_\_

Remarks:

INCLUDE WITHIN APPROVAL LETTER:

Bond Required: ☐

Survey Plat Required: ☐

Order No. 102-16  
102-5 Nov 2 64

Surface Casing Change ☐  
to \_\_\_\_\_

Rule C-3(c), Topographic exception/company owns or controls acreage  
within a 660' radius of proposed site ☐

O.K. Rule C-3 ☐

O.K. In \_\_\_\_\_ Unit

Other:

☒ Letter Written/Approved

#3

hl  
PI plotted





## **SANTA FE ENERGY COMPANY**

ODC DIVISION / AMERICAN NATIONAL BANK BLDG., P.O. BOX 12058, AMARILLO, TX 79101, TELEPHONE: (806) 376-5741

July 26, 1979

UT-13-2

Bowers Oil & Gas Exploration, Inc.  
P.O. Box 636  
Grand Junction, Colorado 81501

Attn: Mr. James E. Bowers

Dear Mr. Bowers:

Santa Fe Energy Company, formerly Oil Development Company of Texas, does not have any objection to the staked location of 367' FSL and 735' FEL of Sec 34, T19S, R23E, 5 LB&M, Grand County, Utah for the Bowers Federal Well #1-34.

Sincerely,

D.D. Oswald, Jr.  
Production Superintendent

DO:kw

**BOWERS OIL & GAS EXPLORATION INC.**

P.O. Box 636

GRAND JUNCTION, CO. 81501

BUS: 303-245-1342

RES: 303-242-6311



July 30, 1979

Utah Oil and Gas Commission  
1588 W. N. Temple  
Salt Lake City, Utah 84116

Attention: Mr. Cleon Fite

RE: Bowers Federal Well #1-34,  
seese sec. 34, T19S, R23E,  
Grand County, Utah

Dear Mr. Fite:

Several months ago Mr. Minder informed us a permit for the captioned well could not be issued because the location was within 200 feet of a  $\frac{1}{4}$   $\frac{1}{4}$   $\frac{1}{4}$  line. Because of extreme topographical conditions, steep dropoffs on all sides, we request an exception to field rule #2-2 cause #102-5 be issued. We request the location, as applied for, be allowed to stand. They only lease within a 660 feet radius not in common with the lease under the proposed location is lease #19037 owned by Santa Fe Energy Co. (formerly Oil Development Co. of Texas). This lease is in sec. 3, T20S, R23E. Santa Fe has no objections to our request (see enclosed letter).

Very truly yours,

*James E. Bowers*  
James E. Bowers  
President

JEB/bz  
Enclosure

**BOWERS OIL & GAS EXPLORATION INC.**

P.O. Box 636

GRAND JUNCTION, CO. 81501

BUS: 303-245-1342

RES: 303-242-6311

August 20, 1979



Utah Oil and Gas Commission  
1588 W. N. Temple  
Salt Lake City, Utah 84116


Attention: Mr. Minder

RE: Exception for location for  
Bowers Federal Well #1-34,  
Sec. 34, T19S, R23E,  
Grand County

Dear Mr. Minder:

Approximately three weeks ago we wrote your office explaining our need for a location exception for the captioned well. Since we need to begin drilling in a short while I was wondering when this request would be acted upon? If there is any other information you need please contact me.

Very truly yours,

  
James E. Bowers  
President

JEB/bz

August 28, 1979

Bowers Oil and Gas Exploration, Inc.  
PO Box 636  
Grand Junction, Colorado 81501

Re: Well No. Bowers Federal 1-34  
Sec. 34, T. 19S., R. 23E.,  
Grand County, Utah

Dear Sir:

We request that you examine your APD on the above referenced well to see if it meets the requirements of Cause No. 102-16 which amends Field Rules 1-2 and 2-2. A copy of the memorandum on the order issued by the Board of Oil, Gas and Mining has been included for your information. Should you wish to pursue this application, please furnish additional information required under Cause No. 102-16 and if necessary, make application to appear before the Board.

If in view of the rule changes you choose to resubmit or withdraw your application, please inform this office so that we may know your decision and act upon it.

Sincerely,

DIVISION OF OIL, GAS AND MINING

Michael T. Minder  
Geological Engineer

MTM:bcm

Enc.

cc

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEYSUBMIT IN DUPLICATE\*  
(Other instructions on re-  
verse side)Form approved.  
Budget Bureau No. 42-R1424.

## SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/> Proposed well APD	5. LEASE DESIGNATION AND SERIAL NO. #14267
2. NAME OF OPERATOR Bowers Oil and Gas Exploration, Inc.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME N/A
3. ADDRESS OF OPERATOR P. O. Box 636, Grand Junction, Colorado 81502	7. UNIT AGREEMENT NAME N/A
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 1780' FEL; 1120' FSL	8. FARM OR LEASE NAME N/A
14. PERMIT NO. N/A	9. WELL NO. Bowers Federal Well #1-34
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 4958' GR	10. FIELD AND POOL, OR WILDCAT Unnamed field
	11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA sec. 34, T19S, R23E, S1B&M
	12. COUNTY OR PARISH Grand
	13. STATE Utah

## 16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

## NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐(Other) ☐PULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐ABANDON\* ☐CHANGE PLANS ☒

## SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☐(Other) ☐REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT\* ☐

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

Due to a change in the State of Utah spacing regulations for this area we will have to change the location of Bowers Federal Well #1-34 from 735' FEL; 367' FSL originally proposed to 1780' FEL; 1120' FSL.

Because there is nothing substantially different between the two drill sites we strongly feel there is no need for another onsite inspection. Attached are a survey plat of the newly proposed location and a new cut/fill diagram. Also included are a new drill pad layout and a new production facilities diagram.

18. I hereby certify that the foregoing is true and correct

SIGNED

*James E. Bowers*

TITLE President

DATE 10-4-79

(This space for Federal or State office use)

APPROVED BY

CONDITIONS OF APPROVAL, IF ANY:

TITLE

DATE

\*See Instructions on Reverse Side

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEYSUBMIT IN DUPLICATE\*  
(Other instructions on reverse side)Form approved.  
Budget Bureau No. 42-R1424.

## SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/> Proposed well APD	5. LEASE DESIGNATION AND SERIAL NO. #14267
2. NAME OF OPERATOR Bowers Oil and Gas Exploration, Inc.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME N/A
3. ADDRESS OF OPERATOR P. O. Box 636, Grand Junction, Colorado 81502	7. UNIT AGREEMENT NAME N/A
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface	8. FARM OR LEASE NAME N/A
14. PERMIT NO. 1780' FEL; 1120' FSL	9. WELL NO. Bowers Federal Well #1-34
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 4958' GR	10. FIELD AND POOL, OR WILDCAT Unnamed field
	11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA sec. 34, T19S, R23E, SLB&M
	12. COUNTY OR PARISH 13. STATE Grand Utah

## 16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

## NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐(Other) ☐PULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐ABANDON\* ☐CHANGE PLANS ☒

## SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☐(Other) ☐REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT\* ☐

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

Due to a change in the State of Utah spacing regulations for this area we will have to change the location of Bowers Federal Well #1-34 from 735' FEL; 367' FSL originally proposed to 1780' FEL; 1120' FSL.

Because there is nothing substantially different between the two drill sites we strongly feel there is no need for another onsite inspection. Attached are a survey plat of the newly proposed location and a new cut/fill diagram. Also included are a new drill pad layout and a new production facilities diagram.



18. I hereby certify that the foregoing is true and correct

SIGNED James E. BowersTITLE PresidentDATE 10-4-79

(This space for Federal or State office use)


APPROVED BY \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY: \_\_\_\_\_

TITLE \_\_\_\_\_

DATE \_\_\_\_\_

\*See Instructions on Reverse Side




SCALE: 1" = 1000'

BOWERS FEDERAL WELL #1-34

Located North 1120 feet from the South boundary and West 1780 feet from the East boundary of Section 34, T19S, R23E, SLB&M.

Elev. 4958

Grand County, Utah



SURVEYOR'S CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF

*[Signature]*  
UTAH R.L.S. NO. 2573




UDELL S. WILLIAMS  
751 Rood Avenue  
GRAND JUNCTION, COLORADO 81501

PLAT OF  
PROPOSED LOCATION  
BOWERS FEDERAL WELL #1-34  
SW $\frac{1}{4}$ SE $\frac{1}{4}$  SECTION 34  
T19S, R23E, SLB&M

SURVEYED BY: USW DATE: 9/26/79

DRAWN BY: USW DATE: 10/02/79

# CUT/FILL DIAGRAM FOR WELL #1-34



DRILL PAD - SCALE 1" = 50'


CUT/FILL SECTIONS NOT DRAWN TO SCALE

EAST/WEST CROSS SECTION






# DRILL PAD LAYOUT FOR BOWERS FEDERAL WELL #1-34

N



PROPOSED PRODUCTION FACILITIES FOR BOWERS FED. WELL #1-34





DIAMOND RIDGE (Jd)  
Kd

UNNAMED (Jm)  
Kd

PEAR PARK (Jm)  
Kd

K CLIFFS UNIT (Jm)  
Kd

BOOK  
CLIFFS UNIT  
GULF OIL

DANISH WASH (Jm)  
Kd

SEIBER NOSE (Jm)  
Kd, Jm

CISCO SPRINGS (Je)  
Kd, Jm

CISCO WASH (Jm)  
Jm

CISCO (Pf)  
Kd, Jm

EAGLE MONUMENT (Jm)  
Jm

DOME (Pe)  
Kcm, Jm

U D

Walter Kearns  
2890 4291  
Kbc 2387

Anderson  
2380 4682  
Je 3154

Vukobovich  
9894 4599  
Jm

Gas Prod  
2803 4703  
Jm 2713

Gas Prod  
3434 4861  
Jm 2171

Pease  
3131 4954  
Jm 2842

Pease  
2920 5020  
Jm 2483

Pease  
2725 4890  
Kcm 2510

Pease  
2659 5298  
Je 1425

Pease  
2600 5604  
Kd 523

Pease  
2580 5664  
Kd 409

Pease  
2544 604  
Jm 5244

Pease  
2524 604  
Jm 5244

Pease  
2524 604  
Jm 5244

Pease  
2524 604  
Jm 5244

Pease  
2524 604  
Jm 5244

LI-34, 2-35 B-35  
LEAST OUTLINE  
#14267

GRAVEL PILE

#1-36

#1-36

#1-36

#1-36

#1-36

#1-36

#1-36

#1-36

#1-36

#1-36

#1-36

#1-36

AGATE (Jm)  
Jm

Steve  
1945 4624  
Jm 2993

Steve  
1945 4624  
Jm 2993

Steve  
1945 4624  
Jm 2993

Steve  
1945 4624  
Jm 2993

Steve  
1945 4624  
Jm 2993

Steve  
1945 4624  
Jm 2993

Steve  
1945 4624  
Jm 2993

Steve  
1945 4624  
Jm 2993

Steve  
1945 4624  
Jm 2993

Steve  
1945 4624  
Jm 2993

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

Texaco  
2605 461  
Jm 295

November 15, 1979

Bowers Oil and Gas Exploration, Inc.  
P.O. Box 636  
Grand Junction, Colorado 81502

Re: Well No. Bowers Federal 1-34  
Sec. 34, T. 19S, R. 23E.,  
Grand County, Utah

Insofar as this office is concerned, approval to drill the above referred to gas well is hereby granted in accordance with the Order issued in Cause No. 102-16 dated August 22, 1979.

Should you determine that it will be necessary to plug and abandon this well, you are hereby requested to immediately notify the following:

MICHAEL T. MINDER  
Geological Engineer  
Office: 533-5771  
Home: 876-3001

Enclosed please find Form OGC-8-8, which is to be completed whether or not water sands (aquifers) are encountered during drilling. Your cooperation in completing this form will be appreciated.

Further, it is requested that this Division be notified within 24 hours after drilling operations commence, and that the drilling contractor and rig number be identified.

The API number assigned to this well is 43-019-30573.

Sincerely,

DIVISION OF OIL, GAS AND MINING

Michael T. Minder  
Geological Engineer

/b:tm

cc: USGS



SCOTT M. MATHESON  
Governor

OIL, GAS, AND MINING BOARD

GORDON E. HARMSTON  
Executive Director,  
NATURAL RESOURCES

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS, AND MINING  
1588 West North Temple  
Salt Lake City, Utah 84116  
(801) 533-5771

CHARLES R. HENDERSON  
Chairman

JOHN L. BELL  
C. RAY JUVELIN  
THADIS W. BOX  
CONSTANCE K. LUNDBERG  
EDWARD T. BECK  
E. STEELE McINTYRE

CLEON B. FEIGHT  
Director

November 21, 1979

James E. Bowers  
Box 636  
Grand Junction, Colo. 81501

Gentlemen:

*Attached is a copy of the final order in Cause No. 102-16B.*

*You will note that this order requires a copy of the property or lease line to be filed with the Application for Permit to Drill. If this only covers the pertinent section, so state.*

*No new Applications for Permit to Drill will be granted unless all required forms on existing wells are up-to date. Also, some operators have not been submitting their 2 mill conservation levy as authorized under Section 40-6-14, Utah Code Annotated, 1953, as amended. The required sales report, Form 5, may be obtained upon request from this office.*

*Sincerely,*

DIVISION OF OIL, GAS AND MINING

*Cleon B. Feight*  
Cleon B. Feight  
Director

/bkm

cc Well Files

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

DUPLICATE COPY

## APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

## 1a. TYPE OF WORK

DRILL ☒DEEPEN ☐PLUG BACK ☐

## b. TYPE OF WELL

OIL  
WELL ☐GAS  
WELL ☒

OTHER

SINGLE  
ZONE ☐MULTIPLE  
ZONE ☐

## 2. NAME OF OPERATOR

Bowers Oil and Gas Exploration, Inc.

## 3. ADDRESS OF OPERATOR

P. O. Box 636, Grand Junction, Colorado 81502

## 4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.\*)

At surface

1780' FEL, 1120' FSL

At proposed prod. zone

same

## 14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE\*

Approximately 10 miles north by northwest of Cisco, Utah

## 15. DISTANCE FROM PROPOSED\*

LOCATION TO NEAREST

PROPERTY OR LEASE LINE, FT.

(Also to nearest drilg. unit line, if any)

1120'

## 16. NO. OF ACRES IN LEASE

2240

## 17. NO. OF ACRES ASSIGNED

TO THIS WELL

160

## 18. DISTANCE FROM PROPOSED LOCATION\*

TO NEAREST WELL, DRILLING, COMPLETED,

OR APPLIED FOR, ON THIS LEASE, FT.

more than 2640 ft.

## 19. PROPOSED DEPTH

2600

## 20. ROTARY OR CABLE TOOLS

Rotary

## 21. ELEVATIONS (Show whether DF, RT, GR, etc.)

4958' GR

## 22. APPROX. DATE WORK WILL START\*

15 Dec., 1979

## 23.

## PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
8 3/4"	7"	20 lbs.	200'	60 sx. Class G; 3% CaCl
6 1/4"	4 1/2"	9.5 lb.	2600'	60 sx. RFC, 10-2

SEE ATTACHED PAPER

RECEIVED

DEC 11 1979

DIVISION OF  
OIL, GAS & MINING

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

## 24.

SIGNED

*James E. Bowers*

TITLE

President

DATE 11-20-79

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE

APPROVED BY

*W. J. Martin*

TITLE

ACTING DISTRICT ENGINEER

DATE

DEC 10 1979

CONDITIONS OF APPROVAL, IF ANY:

\*See Instructions On Reverse Side

10 OPERATIONS COPY

Utah State oil &amp; Gas

U. S. GEOLOGICAL SURVEY CONSERVATION DIVISION  
FROM: : DISTRICT GEOLOGIST, SALT LAKE CITY, UTAH

TO : DISTRICT ENGINEER, O&G, SALT LAKE CITY, UTAH

SUBJECT: APD MINERAL EVALUATION REPORT

LEASE NO. 11 14 267

OPERATOR: Bowers Oil + Gas Exploration

WELL NO. 1-341

LOCATION: 1/4 SE 1/4 SE 1/4 sec. 34, T. 19 S, R. 23 E, S2M

Grand County, Utah

1. Stratigraphy: Mancos shale - surface

Dakota - 2100  
Cedar Mtn - 2200  
Morrison - 2300

2. Fresh Water: none probable.

3. Leasable Minerals:

gas possible - Dakota, Cedar Mtn + Morrison

4. Additional Logs Needed:

adequate

5. Potential Geologic Hazards:

none expected

6. References and Remarks:

Signature: [Signature]

Date: 6 - 1 - 79

Oil and Gas Drilling

EA #353-79

United States Department of the Interior  
Geological Survey  
2000 Administration Bldg.  
1745 West 1700 South  
Salt Lake City, Utah 84104

Usual Environmental Analysis

Lease No.: U-14267

Operator: Bowers Oil & Gas Exploration, Inc. Well No.: 1-34

Location: 1780' FEL & 1120' FSL Sec.: 34 T.: 19S. R.: 23E.

County: Grand State: Utah Field: Wildcat

Status: Surface Ownership: Public Minerals: Federal

Joint Field Inspection Date: November 14, 1979

Participants and Organizations:

Bob Kershaw  
Jim Bowers  
Glenn Doyle

BLM-Moab  
Operator  
USGS-Grand Junction

Related Environmental Analyses and References:

(1) Book Mountain Planning Unit, Resource Analysis. BLM, Moab

Analysis Prepared by: Glenn M. Doyle  
Environmental Scientist  
Grand Junction, Colorado

Date: December 7, 1979

*Pad 200' x 200'  
Pit 30' x 50'  
Access 18' x 800'  
2 access  
mitigators  
(A-C) p. 7*



Proposed Action:

On May 21, 1979, Bowers Oil and Gas Exploration, Inc. filed an Application for Permit to Drill the No. 1-34 development well, a 2550 ft. gas test of the Dakota, Cedar Mountain and Morrison Formation; located at an elevation of 4965 ft. in the SE $\frac{1}{4}$  SE $\frac{1}{4}$  of Section 34, T. 19S., R. 23E. on Federal mineral lands and public surface; lease No. U-14267.

An onsite for this location was conducted and an environmental analysis written. Approval was granted on July 5, 1979.

Subsequent to this action, the State of Utah changed its spacing regulations covering the area. In response to this action, Bowers filed a Sundry Notice on October 4, 1979 detailing a location move of 1045 ft. to the West and 753 ft. to the North.

A second onsite was conducted on November 14, 1979. The operator was informed that a new APD was required for any location moves greater than 200 ft. The operator agreed to submit a new APD.

This environmental analysis, then, applies to the second onsite conducted and to the new APD that has been submitted.

The new location for the Bowers Well No. 1-34 is at 4958 ft. elevation, 1780' FEL and 1120' FSL, Section 34, T. 19S., R. 23E., Grand County, Utah. There was no objection raised to either the wellsite or the access road.

A rotary rig would be used for the drilling. An adequate casing and cementing program is proposed. Fresh-water sands and other mineral-bearing formations would be protected. A Blowout Preventor would be used during the drilling of the well. The proposed pressure rating should be adequate. Details of the operator's NTL-6 10-Point Subsurface Plan are on file in the USGS District Office in Salt Lake City, Utah and the USGS Northern Rocky Mountain Area Office in Casper, Wyoming. The 13-Point Surface Protection Plan is on file in the District Office in Salt Lake City.

A working agreement has been reached with the BLM, the controlling surface agency. Rehabilitation plans would be decided upon as the well neared completion; the Surface Management Agency would be consulted for technical expertise on those arrangements.

The operator proposes to construct a drill pad 200 ft. wide x 200 ft. long and a reserve pit 30 ft x 50 ft. A new access road would be constructed 18 ft. wide x approximately 800 ft. long from couater-maintained road. The operator proposes to construct production facilities on disturbed area of the proposed drill pad.

If production is established, plans for a gas flow line would be submitted to the appropriate agencies for approval. The anticipated starting date is December, 1979 and duration of drilling activities would be about 7 days.

If production is established, a 4½" surface flowline would be constructed approximately 100 ft. to the North, connecting with a North-west Pipeline surface gathering system.

Location and Natural Setting:

The proposed drill site is approximately 10 miles North, Northwest of Cisco, Utah, the nearest town. A fair road runs to within 800 ft. of the location. This well is in a Wildcat field.

Topography:

The wellsite lies in the Cisco Desert which is characterized by generally flat terrain interspersed with rolling hills.

Geology:

The surface geology is Mancos shale.

The soil is a sandy-clay.

No geologic hazards are known near the drillsite.

Seismic risk for the area is minor. Anticipated geologic tops are filed with the 10Point Subsurface Protection Plan.

Approval of the proposed action would be conditioned that adequate and sufficient electric/radioactive/density logging surveys would be made to locate and identify any potential mineral resources. Production casing and cementing would be adjusted to assure no influence of the hydro-carbon zones through the well bore on these minerals. In the event the well is abandoned, cement plugs would be placed with drilling fluid in the hole to assure protection of any mineral resources.

The potential for loss of circulation would exist. Loss of circulation may result in the lowering of the mud levels, which might permit exposed upper formations to blow out or to cause formation to slough and stick to drill pipe. A loss of circulation would result in contamination due to the introduction of drilling muds, mud chemicals, filler materials, and water deep in to the permeable zone, fissures, fractures, and caverns within the formation in which fluid loss is occurring. The use of special drilling techniques, drilling muds, and lost circulation materials may be effective in controlling lost circulation.

A geologic review of the proposed action has been furnished by the Area Geologist, U.S. Geological Survey, Salt Lake City, Utah.

The operator's drilling, cementing, casing and blowout prevention programs have been reviewed by the Geological Survey engineers and determined to be adequate.

Soils:

No detailed soil survey has been made of the project area. The top soils in the area range from a sandy clay to a clay type soil. The soil is subject to runoff from rainfall and has a high runoff potential and sediment production would be high. The soils are mildly to moderately alkaline and support the salt-desert shrub community. The pinyon-juniper association is also present.

8" of top soil will be stockpiled on the South end of the pad, on both sides of the access road. The soil would be spread over the surface of disturbed areas when abandoned to aid in rehabilitation of the surface. Rehabilitation is necessary to prevent erosion and encroachment of undesired species on the disturbed areas. The operator proposes to rehabilitate the location and access roads per the recommendations of the Bureau of Land Management.

Approximately 2 acres of land would be stripped of vegetation. This would increase the erosional potential. Proper construction practice, construction of water bars, reseeding of slope-cut area would minimize this impact.

Air:

No specific data on air quality is available at the proposed location. There would be a minor increase in air pollution due to emissions from rig and support traffic engines. Particulate matter would increase due to dust from travel over unpaved dirt roads. The potential for increased air pollution due to leaks, spills, and fire would be possible.

Relatively heavy traffic would be anticipated during the drilling-operations phase, increasing dust levels and exhaust pollutants in the area. If the well was to be completed for production, traffic would be reduced substantially to a maintenance schedule with a corresponding decrease of dust levels and exhaust pollutants to minor levels. If the project results in a dry hole, all operations and impact from vehicular traffic would cease after abandonment. Due to the limited number of service vehicles and limited time span of their operation, the air quality would not be substantially reduced.

Toxic or noxious gases would not be anticipated. However, if H<sub>2</sub>S or any other toxic substances are encountered, the USGS is to be notified immediately.

Precipitation:

Annual rain fall should range from about 8 to 11" at the proposed location. The majority of the numerous drainages in the surrounding area are of a non-perennial nature flowing only during early spring runoff and during extremely heavy rain storms. This type of storm is rather uncommon as the normal annual precipitation is around 8".

Winds are medium and gusty, occurring predominately from Southwest to Northeast. Air mass inversions are rare. The climate is semi-arid with abundant sunshine, hot summers and cold winters with temperature

variations on a daily and seasonal basis.

#### Surface Water Hydrology:

Drainage from the location would be towards Cottonwood Wash, a non-perennial tributary of the Colorado River.

Some additional erosion would be expected in the area since surface vegetation would be removed. If erosion became serious, drainage systems such as water bars and dikes would be installed to minimize the problem. The proposed project should have minor impact on the surface water systems. The potentials for pollution would be present from leaks or spills. The operator is required to report and clean-up all spills or leaks.

#### Ground Water Hydrology:


Some minor pollution of ground water systems would occur with the introduction of drilling fluids (filtrate) into the aquifer. This is normal and unavoidable during rotary drilling operations. The potential for communication, contamination and comingling of formations via the well bore would be possible. The drilling program is designed to prevent this. There is need for more data on hydrologic systems in the area and the drilling of this well may provide some basic information as all shows of fresh water would be reported. Water production with the gas would require disposal of produced water per the requirements of NTL-2B. The depths of fresh water formations are listed in the 10-Point Subsurface Protection Plan. The pits would be unlined. If fresh water should be available from the well, the owner or surface agency may request completion as a water well if given approval.

#### Vegetation:

A sparse cover of shadscale, four wing saltbush, sagebrush, cacti and grasses are present at the location and along the access route.

Proposed action would remove about 2 acres of vegetation. Removal of vegetation would increase the erosional potential and there would be a minor decrease in the amount of vegetation available for grazing.

The operator proposes to rehabilitate the surface upon completion of operations.

Rehabilitation would be conducted in accordance with BLM recommendations. 

#### Wildlife:

Animal and plant inventory has been made by the BLM. No endangered plants or animals are known to inhabit the project area.

The fauna of the area consists predominantly of mule deer, coyotes, rabbits, foxes, and varieties of small ground squirrels and other types of rodents and various types of reptiles. The area is used by man for the primary purpose of grazing domestic livestock and sheep. The birds of the area are raptors, finches, ground sparrows, magpies, crows, and jays.

#### Social-Economic Effect:

An on the ground surface archaeological reconnaissance would be required prior to approval of the proposed action. Appropriate clearances would then be obtained from the surface managing agency. If a historic artifact, an archaeological feature or site is discovered during construction operations; activity would cease until the extent, the scientific importance, and the method of mitigating the adverse effects could be determined by a qualified cultural resource specialist.

There are no occupied dwellings or other facilities of this nature in the general area. Minor distractions from aesthetics would occur over the lifetime of the project. All permanent facilities placed on the location would be painted a color to blend in with the natural environment. Present use of the area is grazing, recreation, and oil and gas activities.

Noise from the drilling operation may temporarily disturb wildlife and people in the area. Noise levels would be moderately high during drilling and completion operations. Upon completion, noise levels would be infrequent and significantly less. If the area is abandoned, noise levels should return to pre-drilling levels.

The site is not visible from any major roads. After drilling operations, completion equipment would be visible to passersby of the area but would not present a major intrusion.

The economic effect on one well would be difficult to determine. The overall effect of oil and gas drilling and production activity are significant in Grand County.

But should this well discover a significant new hydrocarbon source, local, state, and possible national economics might be improved. In this instance, other development wells would be anticipated, with substantially greater environmental and economic impacts.

Should the wellsite be abandoned, surface rehabilitation would be done according to the surface agency's requirements and to USGS's satisfaction. This would involve leveling, contouring, reseeding, etc., of the location and possibly the access road. If the well should produce hydrocarbons, measures would be undertaken to protect wildlife and domestic stock from the production equipment.

To protect wildcat and livestock from possible toxic fluids, the reserve pit would be 4-strand barbed wire fenced on three sides during drilling and on four sides once the rig has moved off.

There are no national, state, or local parks, forests, wildlife refuges or ranges, grasslands, monuments, trails or other formally designated recreational facilities near the proposed location.

The proposed location is within the Book Mountain Planning Unit. This Environmental Assessment Record was compiled by the Bureau of Land Management, the surface managing agency of the Federal surface in the area. The study includes additional information on the environmental impact of oil and gas operations in this area and gives land use recommendations. The E.A.R. is on file in the agency's State offices and is incorporated herein by reference.

#### Waste Disposal:

The mud and reserves pits would contain all fluids used during the drilling operations. A covered trash pit would be utilized for any solid wastes generated at the site and would be buried at the completion of the operations. Sewage would be handled according to State sanitary codes. For further information, see the 13-Point Surface Plan.

#### Alternative to the Proposed Action:

(1) Not approving the proposed permit-The oil and gas lease grants the lessee exclusive right to drill for, mine, extract, remove and dispose of all oil and gas deposits. Under leasing provisions, the Geological Survey has an obligation to allow mineral development if the environmental consequences are not too severe or irreversible. Upon rehabilitation of the site, the environmental effects of this action would be substantially mitigated, if not totally annulled. Permanent damage to the surface and subsurface would be prevented as much as possible under USGS and other controlling agencies supervision with rehabilitation planning reversing almost all effects. Additionally, the growing scarcity of oil and gas should be taken into consideration. Therefore, the alternative of not proceeding with the proposed action at this time is rejected.

(2) Minor relocation of the wellsite and access road or any special, restrictive stipulations or modifications to the proposed program would not significantly reduce the environmental impact. There are no severe vegetative, animal or archaeological-historical-cultural conflicts at the site. Since only a minor impact on the environment would be expected, the alternative of moving the location is rejected. At abandonment, normal rehabilitation of the area such as contouring, reseeding, etc., would be undertaken with an eventual return to the present status as outlined in the 13-Point Surface Plan.

(3) Drilling should be allowed provided the following mitigative measures are incorporated into the proposed APD and adhered to by the operator.

- A. Operator will stockpile 8" of top soil on the South end of the pad on both sides of the access road.
- B. Operator will fence reserve pit with 4-strand barbed wire on three sides during drilling and on four sides once the rig has moved off.
- C. Operator will maintain blooie line at least 125 ft. away from the well head and direct it into the reserve pit.

Adverse Environmental Effects Which Cannot Be Avoided:

Surface disturbance and removal of vegetation from approximately 2 acres of land surface for the lifetime of the project which would result in increased and accelerated erosional potential. Grazing would be eliminated in the disturbed areas and there would be a minor and temporary disturbance of wildlife and livestock. Minor induced air pollution due to exhaust emissions from rig engines of support traffic engines would occur. Minor increase in dust pollution would occur due to vehicular traffic associated with the operation. If the well is a gas producer, additional surface disturbance would be required to install production pipelines. The potential for fires, gas leaks, and spills of oil and water would exist. During the construction and drilling phases of the project, noise levels would increase. Potential for sub-surface damage to fresh water aquifers and other geologic formations exists. Minor distractions from aesthetics during the lifetime of the project would exist. If the well is a producer, an irreplaceable and irretrievable commitment of resources would be made. Erosion from the site would eventually be carried as sediment in the Colorado River. The potential for pollution to the Cottonwood Wash would exist through leaks and spills.

If the well is a producer, other development wells would be anticipated with substantially greater environmental and economic impacts.

Determination:

This requested action does not constitute a major Federal action significantly affecting the environment in the sense of NEPA, Section 102 (2) (C).

**DEC 10 1979**

Date

**ACTING**

*WP Martin*  
District Engineer  
U.S. Geological Survey  
Conservation Division  
Oil and Gas Operations  
Salt Lake City District



Photo #1-34



102 III NW  
(FLUME CANYON)

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY


109° 22' 30"  
39° 07' 30"

641000m E

442

443

44 20'



**BOWERS OIL & GAS EXPLORATION INC.**

P.O. Box 636

GRAND JUNCTION, CO. 81501

BUS: 303-245-1342

RES: 303-242-6311

SURFACE USE PLAN (NTL-6)

1. Existing Roads - (see attached map).

- a. Proposed well site is marked. 200 ft., north, south directioned reference stakes have been laid.
- b. Route and distance from nearest town or locatable reference point to where well access route leaves main road -

From Grand Junction, CO. you take I-70 west until you come to the east Cisco exit (a distance of approx. 50 miles). You turn right off of the exit and proceed in a northerly direction for approx. 5 miles. This distance will have brought you to our access road where you turn left and travel about 300 ft. to the proposed location.

- c. Access road to location color-coded or labeled -

Access road is labeled (see attached map).

- d. If exploratory well, all existing roads within 3-mile radius  
N/A.

- e. If development well, all existing roads within a 1-mile radius of well site (including type of surface, conditions, etc.)

There are two such roads. The first is a light duty, hard surface road. It is the road described in 1.b. above. It is located approx. 300 ft. from the proposed location (see attached maps). The second is an unimproved dirt road located approx. one mile NE of the proposed location. This road begins in section 33 where it exits the other existing road. This second road runs in a SW/NE direction (see attached map.)

- f. Plans for improvement and/or maintenance of existing roads -

There are no plans for improvements and/or maintenance of existing roads.

2. Planned Access Roads

Enclosed is a map showing the one access road which needs to be constructed. No access road needs to be reconstructed.

- (1) Width - The road will be 15-18 ft. wide.
- (2) Maximum grade - The maximum grade will be 3%.

### Planned Access Roads (cont.)

- (3) Turnouts - No turnouts will be needed.
- (4) Drainage design - None needed.
- (5) Location and size of culverts and brief description of any major cuts and fills - No culverts are needed. No major cuts or fills are needed, (see attached diagram).
- (6) Surfacing material - No foreign material will be put on the access road. The native soil will provide an adequate surface.
- (7) Necessary gates, cattleguards, or fence cuts - No gates nor cattleguards will need to be built. No fences will need to be cut.
- (8) The access road is center-line flagged.

### 3. Location of Existing Wells

The following is a list of various types of wells located within a one-mile radius of the location: (also, see attached map)

- (1) Water wells - There are no water wells within the one-mile radius.
- (2) Abandoned wells -
  - a. SW $\frac{1}{4}$  sec. 2, T20S, R23E
  - b. NW $\frac{1}{4}$  sec. 34, T19S, R23E
  - c. SE $\frac{1}{4}$  sec. 27, T19S, R23E
  - d. SW $\frac{1}{4}$  sec. 26, T19S, R23E
- (3) Temporarily abandoned wells - There are no temporarily abandoned wells within a one-mile radius.
- (4) Disposal Wells - There are no disposal wells within a one-mile radius.
- (5) Drilling Wells - There are no drilling wells within a one-mile radius.
- (6) Producing Wells - There are no producing wells within a one-mile radius.
- (7) Shut-in Wells - There are no shut-in wells within a one-mile radius.
- (8) Injection Wells - There are no injection wells within a one-mile radius.
- (9) Monitoring or observation wells for other resource - There are no monitoring or observation wells for other resources within a one-mile radius.

### 4. Location of Existing and/or Proposed Facilities-

#### A. Within a one-mile radius of location show the following existing facilities owned or controlled by operator/lessee.

- (1) Tank batteries - None owned or controlled by operator/lessee.
- (2) Production facilities - None owned or controlled by operator/lessee.
- (3) Oil gathering lines - none owned or controlled by operator/lessee.

- (4) Gas gathering lines - None owned or controlled by operator/lessee.
- (5) Injection lines - None owned or controlled by operator/lessee.
- (6) Disposal lines - None owned or controlled by operator/lessee.

(Indicate if any of the above lines are buried) - N/A

B. If new facilities are contemplated, in the event of production, show:

- (1) Proposed location and attendant lines by flagging if off of well pad - Flagged stakes from the well location to N.W. Pipeline Co.'s feeder line has been set. This route would be the proposed gas pipeline route if commercial natural gas is found.
- (2) Dimensions of facilities - A gas-meter housing facility would be no more than 50' x 50'. Its purpose would be for measuring the volume of gas produced. A 4½" pipeline (buried) would run from this meter station to N.W. Pipeline's gathering system on the route described in B.1. above. Approx. five feet on either side of the pipeline route would be needed for installation.
- (3) Construction methods and materials - The meter house would be a metal, pre-fabricated structure painted desert gold. Inside would be valves, fittings, meter runs, chart, etc. needed to measure the volume of gas. The pipeline would be 4½" O.D. pipe.
- (4) Protective measures and devices to protect livestock and wildlife - It is believed neither the wellhead, nor the meter house nor the pipeline would present a danger to wildlife. If water is produced a 4 ft. fence w/steel posts will be built around the reserve pit. (We do not anticipate encountering oil. If commercial oil is found, however, we will present a proposed oil production facility by use of a sundry notice.)

C. Plan for rehabilitation of disturbed areas no longer needed for operations after construction completed - We plan to contour all of the topsoil back over the disturbed areas that is no longer needed after operations are ended. We will then reseed in a quantity, method and with the type of seed the BLM recommends.

5. Location and type of Water Supply

- A. Show location and type of water supply either on map or by written description - We will obtain fresh water from the Colorado River north of Cisco, Utah or from a drinking water tap in Fruita, CO. Fruita, CO. is located west of Grand Junction, as described above and also exits off I-70. Cisco, Utah can be reached by turning left off the east Cisco exit (as you travel west on I-70). Go approx. 3½ miles south on highway 50. The turnoff to the River is approx. ½ mile from Cisco. You turn left off of highway 50 on an unimproved dirt road and travel approximately 3 miles.
- B. State method of transporting water, and show any roads or pipelines needed - We will transport water by water truck. The roads needed are described in 5.A. No new roads will be constructed. No pipelines will be needed.
- C. If water well is to drilled, so state - No water well will be drilled.

6. Source of Construction Materials -

- A. Show information either on map or by written description -  
No entraneous material will be brought in. The native soil will be used as the pad base.
- B. Identify if from Federal or Indian land - N/A
- C. Describe where materials, such as sand, gravel, stone and soil material, are to be obtained and used - As explained in 6.A. the native soil will be used as the pad base. We will not use other materials such as sand, gravel or stone.
- D. Show any needed access roads crossing Federal or Indian lands under item 2 - The only access road will be the one described in (2). It will cross Federal land. (See attached map.)

7. Methods for Handling Waste Disposal -

Describe methods and location of proposed containment and disposal of waste material, including):

- (1) Cuttings - We will blow the cuttings into a reserve pit (the pit is shown on the attached diagram.)
- (2) Drilling fluids - The drilling fluids will be contained in two large steel tanks. The fluids will be disposed into the reserve pit when drilling operations are over.
- (3) Produced fluids - (oil, water) - Produced water will be run into the reserve pit. Oil will also be disposed into the reserve pit unless a large enough amount is produced. If a large amount is produced we will contain it in steel tanks.
- (4) Sewage - Will be disposed of by use of toilet facilities in a mobile home or use of facilities in Cisco, Utah.
- (5) Garbage or other waste material - Will be contained in plastic bags and taken from site when operations end or burned/buried in a trash/burn pit which will be fenced with small mesh wire.
- (6) Statement regarding proper cleanup of well site area when rig moves out  
We will completely clean-up site within two (2) days after rig moves out.

8. Ancillary Facilities - No camps or airstrips will be needed.

9. Well Site Layout - (See attached plot). Pits will be unlined.

10. Plans for Restoration of Surface -

- (1) Backfilling, leveling, contouring, and waste disposal; segregation of spoils materials as needed - All pits will be backfilled. We will contour the topsoil, no longer needed, over that portion of the pad which is no longer needed. The fluids contained in the reserve pit will be buried as will the trash in the trash/burn pit. Appreciable amounts of waste or produced fluids will be hauled from the site rather than buried.
- (2) Revegetation and rehabilitation - We will reseed all disturbed areas, including the access road, in a manner and with the type and quantity


- (2) cont.  
of seed that BLM directs.
- (3) Prior to rig release, pits will be fenced and so maintained until clean up.
- (4) If there is oil on pit we will remove oil or install overhead flagging.
- (5) We will commence rehab. operations within one week after operations end and complete rehab. within one week after starting rehab. (except for reseed-  
ing which will be done when BLM so directs).

11. Other Information

- (1) Topography, soil characteristics, geologic features, flora and fauna - The location is on a mesa located approx. ½ mile north of a steep drop-off (see attached map). The soil in this area varies from that containing appreciable amounts of clays to a sand/gravel mixture. The plant life consists mainly of sagebrush with small amounts of native grass. The animal life consists of prairie dogs and jack rabbits.
  - (2) Other surface - use activities and surface ownership of all involved lands - The surface land is used for winter grazing of sheep and cattle. The surface land is federally owned.
  - (3) Proximity of water, occupied dwellings, archeological, historical or cultural sites - The only water supply in the area is Cisco Springs, located approximately three miles SE of the proposed location. The only occupied dwellings are located in Cisco, Utah, the distance and route to are describe above (5). There are no archeological, historical or cultural sites in the area.
12. Lessee's or operator's representative - The operator's representative is James E. Bowers, P.O. Box 636, Grand Junction, Colorado 81501, telephone number: 303-245-1342.
13. Certification - I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and, that the work associated with the operations proposed herein will be performed by Bowers Oil and Gas Exploration, Inc, and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved.


4/25/79  
Date

James E. Bowers  
James E. Bowers, President, Bowers Oil  
and Gas Exploration, Inc.



Compressor

Check valve




Kill Line

From mud pump



GRANT ROTATING HEAD

Hydraulic line




Regan Torus  
Blowout preventer  
3,000 psi WP

Flow line  
Fillup line



Kill line




To chokes and pit

Ground level

7" casing head

7" surface pipe



**BOWERS OIL & GAS EXPLORATION INC.**

P.O. Box 636  
GRAND JUNCTION, CO. 81501  
BUS: 303-245-1342  
RES: 303-242-6311

NTL-6

1. Geologic name of surface formation - mancos shale.
2. Estimated tops of important geologic markers -
  - a. Dakota - 2100 ft.
  - b. Morrison- 2300 ft.
  - c. Morrison (salt wash member)-2500 ft.
3. The estimated depths at which anticipated water, oil, gas or other mineral - bearing formations are expected to be encountered -
  - a. Dakota, 2100 ft., gas or water is expected.
  - b. Cedar Mountain, 2200 ft., gas is expected.
  - c. Morrison (salt wash member), 2500 ft., gas or water is expected.
4. The proposed casing program, including the size, grade, and weight/ft. of each string and whether new or used.
  - a. The surface pipe will be new and graded H-40.  
Other information regarding this pipe is listed in #23, first page of APD.
  - b. The production pipe if needed, will be new and graded H-40.  
Other information regarding this pipe is also listed in #23, first page of APD.
5. The operator's minimum specifications for pressure control equipment which is to be used, a schematic diagram thereof showing sizes, pressure ratings, and the testing procedures and testing frequency -
  - a. A Schaeffer blowout prevents w/Grants rotating head will be used.  
This BOP is rated to 3,000 psi.
  - b. See attached schematic diagram.
  - c. Unit will be tested to 1000 psi. prior to drilling out from under surface pipe by pressuring-up air-compressors. Daily testing will be performed thereafter.
6. The type and characteristics of the proposed circulating medium or mediums to be employed for rotary drilling and the quantities and types of mud and weighting material to be maintained.
  - a. We propose to drill with air as far as possible. If water is encountered we will continue with air/mist. If excessive gas is encountered we will mud-up with high yield gel and drispack system circulated with 4% KCL. At TD we will mud-up with the same system even if excessive gas is not encountered. The mud weight will be between 8.5 lbs/ft. and 9.0 lbs./ft. If a heavier mud is needed we will add CaCl as needed.



7. Auxiliary equipment to be used.
  - a. Kelly cocks.
  - b. Floats at the bit.
  - c. Visual monitoring of the mud system (when used).
  - d. A sub on the rig floor with full opening valve to be stabbed into drill pipe when kelly is out of string.
8. The testing, logging, and coring programs to be followed with provision made for required flexibility:
  - a. No drill stem tests or coring programs are anticipated.
  - b. Visual examination of cuttings will be made.
  - c. Logging will consist of dual induction-laterlog, and compensated neutron/formation density.
9. Any anticipated abnormal pressures or temperatures expected to be encountered or potential hazards such as hydrogen sulfidgas, along with plans for mitigating such hazards -

None expected.
10. The anticipated starting date and duration of the operation -

We plan to start June 1, 1979. Operation should take seven (7) days.

**BOWERS OIL & GAS EXPLORATION INC.**


P.O. Box 636

GRAND JUNCTION, CO. 81501

BUS: 308-248-1342

RES: 308-248-6911

*PROPOSED PRODUCTION FACILITY*  
*Bowers Fed. Well #1-34*



↑ Northwest Pipeline's  
4 1/2" feeder line

1 inch = 50 ft.

**BOWERS OIL & GAS EXPLORATION INC.**


P.O. Box 836

GRAND JUNCTION, CO. 81501

BUS: 303-246-1342

RES: 303-246-6311

*PROPOSED PRODUCTION FACILITY*  
*Bowers Fed. Well #1-34*



Northwest Pipeline's  
4 1/2" feeder line

1 inch = 50 ft.


**BOWERS OIL & GAS EXPLORATION INC.**

P.O. Box 996

GRAND JUNCTION, CO. 81501

Bus: 303-242-1342

Res: 303-242-0511



**BOWERS OIL & GAS EXPLORATION INC.**

P.O. Box 636

GRAND JUNCTION, CO. 81501

BUS: 303-245-1342

RES: 303-242-6311

NTL-6

1. Geologic name of surface formation - mancos shale.
2. Estimated tops of important geologic markers -
  - a. Dakota - 2100 ft.
  - b. Morrison- 2300 ft.
  - c. Morrison (salt wash member)-2500 ft.
3. The estimated depths at which anticipated water, oil, gas or other mineral - bearing formations are expected to be encountered -
  - a. Dakota, 2100 ft., gas or water is expected.
  - b. Cedar Mountain, 2200 ft., gas is expected.
  - c. Morrison (salt wash member), 2500 ft., gas or water is expected.
4. The proposed casing program, including the size, grade, and weight/ft. of each string and whether new or used.
  - a. The surface pipe will be new and graded H-40.  
Other information regarding this pipe is listed in #23, first page of APD.
  - b. The production pipe if needed, will be new and graded H-40.  
Other information regarding this pipe is also listed in #23, first page of APD.
5. The operator's minimum specifications for pressure control equipment which is to be used, a schematic diagram thereof showing sizes, pressure ratings, and the testing procedures and testing frequency -
  - a. A Schaeffer blowout prevents w/Grants rotating head will be used. This BOP is rated to 3,000 psi.
  - b. See attached schematic diagram.
  - c. Unit will be tested to 1000 psi. prior to drilling out from under surface pipe by pressuring-up air-compressors. Daily testing will be performed thereafter.
6. The type and characteristics of the proposed circulating medium or mediums to be employed for rotary drilling and the quantities and types of mud and weighting material to be maintained.
  - a. We propose to drill with air as far as possible. If water is encountered we will continue with air/mist. If excessive gas is encountered we will mud-up with high yield gel and drispack system circulated with 4% KCL. At TD we will mud-up with the same system even if excessive gas is not encountered. The mud weight will be between 8.5 lbs/ft. and 9.0 lbs./ft. If a heavier mud is needed we will add CaCl as needed.

7. Auxiliary equipment to be used.
  - a. Kelly cocks.
  - b. Floats at the bit.
  - c. Visual monitoring of the mud system (when used).
  - d. A sub on the rig floor with full opening valve to be stabbed into drill pipe when kelly is out of string.
8. The testing, logging, and coring programs to be followed with provision made for required flexibility:
  - a. No drill stem tests or coring programs are anticipated.
  - b. Visual examination of cuttings will be made.
  - c. Logging will consist of dual induction-laterlog, and compensated neutron/formation density.
9. Any anticipated abnormal pressures or temperatures expected to be encountered or potential hazards such as hydrogen sulfidgas, along with plans for mitigating such hazards -

None expected.
10. The anticipated starting date and duration of the operation -

We plan to start June 1, 1979. Operation should take seven (7) days.

**BOWERS OIL & GAS EXPLORATION INC.**

P.O. Box 696


GRAND JUNCTION, CO. 81501

Bus: 300-345-1342

Reg: 300-345-0311

*Location, Bowers  
Fed. Well # 1-34*

*N*



DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

NAME OF COMPANY: Bowers Oil and Gas

WELL NAME: Bowers Federal #1-34

SECTION 34 SW SE TOWNSHIP 19S RANGE 23E COUNTY Grand

DRILLING CONTRACTOR Starner Drilling Company

RIG # 1

SPUDDED: DATE 12/13/79

TIME 2:00 p.m.

HOW rotary

DRILLING WILL COMMENCE 12/15/79

REPORTED BY James Bowers

TELEPHONE #

DATE December 14, 1979

SIGNED M. J. Menden

cc: USGS



March 3, 1980

Bowers Oil and Gas Exploration, Inc.  
P.O. Box 636  
Grand Junction, Colorado 81502

Re: Well No. Fed. 1-34  
Sec. 34, T. 19S, R. 23E.  
Grand County, Utah  
January-February 1980

Gentlemen:

Our records indicate taht you have not filed the monthly drilling reports for the months indicated above on the subject well.

Rule C-22, General Rules and Regulations and Rules of Practice and Procedure, requires that said reports be filed on or before the sixteenth (16) day of the succeeding month. This report may be filed on Form OGC-1B, (U.S. Geological Survey Form 9-331) "Sundry Notices and Reports on Wells", or on company forms containing substantially the same information. We are enclosing forms for your convenience.

Your prompt attention to the above will be greatly appreciated.

Very truly yours,

DIVISION OF OIL, GAS, AND MINING



JANICE TABISH  
CLERK TYPIST

File

FILE IN TRIPLICATE  
FORM OGC-8-X

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING  
1588 West North Temple  
Salt Lake City, Utah 84116

\*\*REPORT OF WATER ENCOUNTERED DURING DRILLING\*\*

Well Name & Number Bowers Federal Well #1-34  
Operator Bowers Oil & Gas Exploration, Inc. Address P. O. Box 636, Grand Junction, CO  
81502  
Contractor Starnier Drilling Co. Address 715 Horizon Drive, Grand Junction, CO  
81502  
Location SW 1/4 SE 1/4 Sec. 34 T. 19S R. 23E County Grand

Water Sands

	<u>Depth</u>	<u>Volume</u>	<u>Quality</u>
	From To	Flow Rate or Head	Fresh or Salty
1.	2200' - 2226'	10 BWPD	Salty
2.			
3.			
4.			
5.			

(Continue on reverse side if necessary)

Formation Tops

2155' (KB)-Dakota

2294' (KB)-Cedar Mountain

Remarks

2424' (KB)-Morrison

**RECEIVED**

MAR 10 1980

DIVISION OF  
OIL, GAS & MINING

- NOTE: (a) Report on this form as provided for in Rule C-20, General Rules and Regulations and Rules of Practice and Procedure.  
(b) If a water analysis has been made of the above reported zone, please forward a copy along with this form.



# DOWELL DIVISION OF THE DOW CHEMICAL COMPANY

DENVER REGION

## API WATER ANALYSIS REPORT FORM

DATE Jan. 10, 1980

LAB NO. CL 8308

ER

Company <b>Jim Bowers Oil &amp; Gas Co.</b>		Sample No. <b>73267</b>		Date Sampled	
Field <b>Cisco</b>		Legal Description		County or Parish <b>Grand</b>	State <b>Utah</b>
Lease or Unit <b>Federal</b>	Well <b>1-34</b>	Depth <b>2418</b>	Formation <b>Morrison</b>	Water, B/D	
Type of Water (Produced, Supply, etc.)			Sampling Point		Sampled By

### DISSOLVED SOLIDS

CATIONS	mg/l	me/l
Sodium, Na (calc.)	13159	579.0
Calcium, Ca	1900	95.0
Magnesium, Mg	210	16.8
Barium, Ba		


### OTHER PROPERTIES

pH	6.9
Specific Gravity, 60/60 F.	1.031
Resistivity (ohm-meters) — F.	*
BHT	90°F

### ANIONS

Chloride, Cl	24500	686.0
Sulfate, SO <sub>4</sub>	40	0.8
Carbonate, CO <sub>3</sub>	0	
Bicarbonate, HCO <sub>3</sub>	250	4.0

### WATER PATTERNS — me/l



Total Dissolved Solids (calc.)

40059

Iron, Fe (total)

2050

Sulfide, as H<sub>2</sub>S

REMARKS & RECOMMENDATIONS: Sample #2

*D R Mitchell*  
D. R. Mitchell  
DRM/ml

*Possibility of emulsion*

G. Horstman  
D15 - Denver Regional Office  
Sales - Casper Office File  
Tulsa - Earl Morris

\* 0.31 from sample #1  
0.345 - ✓ #4

**RECEIVED**

MAR 10 1980

DIVISION OF  
OIL, GAS & MINING

ANALYSIS BASED ON API RECOMMENDED PROCEDURE

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

SUBMIT IN DUPLIC.

(See other in-  
structions on  
reverse side)Form approved.  
Budget Bureau No. 42-R355.8

15

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG \*

1a. TYPE OF WELL:		OIL WELL <input type="checkbox"/>	GAS WELL <input checked="" type="checkbox"/>	DRY <input type="checkbox"/>	Other <input type="checkbox"/>		
b. TYPE OF COMPLETION:		NEW WELL <input checked="" type="checkbox"/>	WORK OVER <input type="checkbox"/>	DEEP-EN <input type="checkbox"/>	PLUG BACK <input type="checkbox"/>	DIFF. RESVR. <input type="checkbox"/>	Other <input type="checkbox"/>
2. NAME OF OPERATOR						5. LEASE DESIGNATION AND SERIAL NO.	
Bowers Oil and Gas Exploration, Inc.						U-14267	
3. ADDRESS OF OPERATOR						6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
P. O. Box 636, Grand Junction, CO 81502						N/A	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)*						7. UNIT AGREEMENT NAME	
At surface SWSE Sec. 34, T19S, R23E						N/A	
At top prod. interval reported below Same as Above						8. FARM OR LEASE NAME	
At total depth Same as Above						N/A	
14. PERMIT NO.						9. WELL NO.	
43-019-30573						Bowers Fed. Well #1-34	
DATE ISSUED						10. FIELD AND POOL, OR WILDCAT	
11-15-79						Unnamed	
15. DATE SPUDDED						11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA	
12-13-79						Sec. 34, T19S, R23E	
16. DATE T.D. REACHED						SLB & M	
12-17-79						12. COUNTY OR PARISH	
17. DATE COMPL. (Ready to prod.)						Grand	
2-1-80						13. STATE	
18. ELEVATIONS (DF, RKB, RT, OR, ETC.)*						Utan	
4967' KB						19. ELEV. CASINGHEAD	
20. TOTAL DEPTH, MD & TVD						2'	
2721' KB (MD)						21. PLUG, BACK T.D., MD & TVD	
2461' KB PBTD (MD)						22. IF MULTIPLE COMPL., HOW MANY*	
N/A						23. INTERVALS DRILLED BY	
24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)*						ROTARY TOOLS	
2405' - 2418' MD Cedar Mountain						CABLE TOOLS	
25. WAS DIRECTIONAL SURVEY MADE						0-2721'	
NO						26. TYPE ELECTRIC AND OTHER LOGS RUN	
Dual Induc./Laterolog; Comp. Neutron-Formation Density Cement Bond						27. WAS WELL CORED	
28. CASING RECORD (Report all strings set in well)						No	
CASINO SIZE		WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD		AMOUNT PULLED
8 5/8	24	210' KB	11"	100 SX Class B			N/A
4 1/2	10.5	2502' KB	6 3/4"	100 SX REC; 50 SX neat (class G)			N/A
29. LINER RECORD				30. TUBING RECORD			
SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
N/A					1 1/2 "	2350.41'	N/A
31. PERFORATION RECORD (Interval, size and number)				32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.			
2405' - 2418' (KB); 2 jspf, 13 gram, 3/8"				DEPTH INTERVAL (MD)			
				2405' - 2415'			
				AMOUNT AND KIND OF MATERIAL USED			
				24 Bbls. 15% MSR Acid			
				800 SCF N2/bbl.			
33. *As of 2-1-80 well will only flow intermittingly (loaded up with formation water).							
DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)				WELL STATUS (Producing or shut-in)	
						O.S.	
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.	GAS—MCF.	WATER—BBL.	GAS-OIL RATIO
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.	WATER—BBL.	API (CORR.)	
34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)						TEST WITNESSED BY	
						MAR 10 1980	
35. LIST OF ATTACHMENTS							
Report of stuck packer.							
36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.							
SIGNED		JAMES E. BOWERS		TITLE		President	
						DIVISION OF OIL, GAS & MINING	
						DATE 2-25-80	

\*(See Instructions and Spaces for Additional Data on Reverse Side)

# INSTRUCTIONS

**General:** This form is designed for submitting a complete and correct well completion report and log on all types of lands and leases to either a Federal agency or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office. See instructions on items 22 and 24, and 33, below regarding separate reports for separate completions.

**Item 18:** Indicate which elevation is used as reference (where not otherwise shown) for depth measurements given in other spaces on this form and in any attachments. Items 22 and 24: If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals; top(s), bottom(s) and name(s) (if any) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

**Item 29:** "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

**Item 33:** Submit a separate completion report on this form for each interval to be separately produced. (See instruction for items 22 and 24 above.)

37. SUMMARY OF POROUS ZONES: SHOW ALL IMPORTANT ZONES OF POROSITY AND CONTENTS THEREOF; CORED INTERVALS; AND ALL DRILL-STEM TESTS, INCLUDING DEPTH INTERVAL TESTED, CUSHION USED, TIME TOOL OPEN, FLOWING AND SHUT-IN PRESSURES, AND RECOVERIES				38. GEOLOGIC MARKERS	
FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	MEAS. DEPTH
Dakota	2200' KB	2226' KB	Water (Brackish, 10 BWP estimated)	Dakota	2155' KB
Cedar Mtn. Dakota	2270' KB	2290' KB	Gas (100 m.c.f. G.P.D. est.)	Cedar Mtn.	2294' KB
Cedar Mtn.	2404' KB	2418' KB	Gas (700 m.c.f. G.P.D. est.)	Morrison	2424' KB
Morrison	2504' KB	2518' KB	Nothing.		
Morrison	2650	2664' KB	Nothing.		

**BOWERS OIL & GAS EXPLORATION INC.**

P.O. Box 636

GRAND JUNCTION, CO. 81502

BUS: 303-245-1342

RES: 303-242-6311

Before this well was acidized, a packer (MSOT Model 32-A Tension type (6-73)) was set at 2374' K.B. After the acid job was completed we attempted to unseat and then retrieve the packer. It would not release. After two days of trying to retrieve the packer we decided it was futile to try further. We shot off the tubing at 2361' K.B. with a 1-13/16" O.D. jet tubing cutter.

*James E. Bowers Pres.*

# GEOLOGICAL SURVEY (FORM 9-329) (2/76) OMB 42-RO 356

## MONTHLY REPORT OF OPERATIONS

Communitization Agreement No. N/A  
 Field Name Unnamed  
 Unit Name N/A  
 Participating Area N/A  
 County Grand State Utah  
 Operator Bowers Oil and Gas Explorations, Inc.  
☐ Amended Report

The following is a correct report of operations and production (including status of all unplugged wells) for the month of January, 19 80

(See Reverse of Form for Instructions)

This report is required by law (30 U.S.C. 189, 30 U.S.C. 359, 25 U.S.C. 396 d), regulation (30 CFR 221.60), and the terms of the lease. Failure to report can result in the assessment of liquidated damages (30 CFR 221.54 (j)), shutting down operations, or basis for recommendation to cancel the lease and forfeit the bond (30 CFR 221.53).

Well No.	Sec. & 1/4 of 1/4	TWP	RNG	Well Status	Days Prod.	*Barrels of Oil	*MCF of Gas	*Barrels of Water	Remarks
Bowers Federal #1-34	SWSE	19S	23E	GSI	None	None	None	None	1-5-80 Perforated well. 1-24-80 Acidized well.

RECEIVED

MAR 10 1980

DIVISION OF  
OIL, GAS & MINING

\*If none, so state.

### DISPOSITION OF PRODUCTION (Lease, Participating Area, or Communitized Area basis)

	Oil & Condensate (BBLS)	Gas (MCF)	Water (BBLS)
*On hand, Start of Month	None	XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX
*Produced	None	None	None
*Sold	None	None	XXXXXXXXXXXXXXXXXX
*Spilled or Lost	None	XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX
*Flared or Vented	XXXXXXXXXXXXXXXXXX	None	XXXXXXXXXXXXXXXXXX
*Used on Lease	None	None	XXXXXXXXXXXXXXXXXX
*Injected	None	None	None
*Surface Pits	XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX	None
*Other (Identify)	None	None	None
*On hand, End of Month	None	XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX
*API Gravity/BTU Content	N/A	N/A	XXXXXXXXXXXXXXXXXX

Authorized Signature: James E. Bowers Address: P. O. Box 636, Grand Junction, CO 81502  
 Title: President

Page 1 of 1

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEYSUBMIT IN TRIPLICATE\*  
(Other instructions on reverse side)Form approved.  
Budget Bureau No. 42-R1424.

5. LEASE DESIGNATION AND SERIAL NO.

71-14267

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

N/A

7. UNIT AGREEMENT NAME

N/A

8. FARM OR LEASE NAME

N/A

9. WELL NO.

Bowens Fed. Well #1-34

10. FIELD AND POOL, OR WILDCAT

Unnamed

11. SEC., T., R., E., M., OR BLK. AND  
SURVEY OR AREA

Sec. 34, T19S, R23E, SLB &amp; M

12. COUNTY OR PARISH

Grand

13. STATE

Utah

SUNDRY NOTICES AND REPORTS ON WELLS  
(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)1. OIL WELL ☐ GAS WELL ☒ OTHER

2. NAME OF OPERATOR

Bowers Oil &amp; Gas Exploration, Inc.

3. ADDRESS OF OPERATOR

P. O. Box 636, Grand Junction, CO 81502

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.\*  
See also space 17 below.)  
At surface

1780 FEL, 1120' FSL

14. PERMIT NO.

43-019-30573

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

4967' KB

## 18. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

## NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐(Other) ☐PULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐ABANDON\* ☒CHANGE PLANS ☐

## SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☐(Other) ☐REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT\* ☐(NOTE: Report results of multiple completion on Well  
Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

- The well was originally completed as a Cedar Mountain Formation gas producer from the perforated interval 2405' - 2415' KB.
- It was found the well produces too much water to be commercial.
- The tops are: Dak. - 2155'; Cedar Mountain - 2294'; Morrison - 2424'.
- We propose to P & A as follows: a) Shoot off and pull as much 4½" casing (est. 2000') as possible. b) Set plugs through tubing: 1. Plug #1 - 2305' to 2515' (20 SK. class B cement). 2. Plug #2 - 200 plug across 4½" cut off (20 SX.) 3. Plug #3 - 210' up to 85' across 7" surface pipe (10SX.) 4. Plug #4 - Surface plug (10SX.) with regulation marker. 5. Hole will be filled with 9ppg. mud.

APPROVED BY THE DIVISION OF  
OIL, GAS, AND MINING

DATE: 5-1-80

BY: M. J. Mincher

18. I hereby certify that the foregoing is true and correct

SIGNED

James E. Bowers

TITLE President

(This space for Federal or State office use)

APPROVED BY

TITLE

CONDITIONS OF APPROVAL, IF ANY:

DATE 4-14-80

APR 18 1980

\*See Instructions on Reverse Side

DIVISION OF  
OIL, GAS & MINING



DIVISION OF OIL, GAS AND MINING

PLUGGING PROGRAM

NAME OF COMPANY: Bowers Oil and Gas Exploration, Inc.

WELL NAME: Bowers Federal #1-34

SECTION 34 SW SE TOWNSHIP 19S RANGE 23E COUNTY Grand

VERBAL APPROVAL GIVEN TO PLUG AND ABOVE REFERRED TO WELL IN THE FOLLOWING MANNER:

TOTAL DEPTH: 2721'

CASING PROGRAM:

8 5/8" @ 210'

4 1/2" @ 2502'

FORMATION TOPS:

Dakota 2155'

Cedar Mtn 2294'

Morrison 2424'

*write for report of  
handment*

PLUGS SET AS FOLLOWS:

#1 2305' - 2515'

#2 200' plug across cutoff @ 2-00'

#3 210' - 85'

#4 30' - surface

DATE May 1, 1980

SIGNED \_\_\_\_\_

Original Signed By M. T. Minder

cc: USGS



SCOTT M. MATHESON  
Governor

GORDON E. HARMSTON  
*Executive Director,*  
NATURAL RESOURCES

CLEON B. FEIGHT  
*Director*

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS, AND MINING  
1588 West North Temple  
Salt Lake City, Utah 84116  
(801) 533-5771  
June 3, 1980

OIL, GAS, AND MINING BOARD

CHARLES R. HENDERSON  
*Chairman*

JOHN L. BELL  
C. RAY JUVELIN  
THADIS W. BOX  
CONSTANCE K. LUNDBERG  
EDWARD T. BECK  
E. STEELE MCINTYRE

Bowers Oil & Gas Exploration, Inc.  
P.O. Box 636  
Grand Junction, Colorado 81502

Re: **Well No. Bowers Federal #1-34**  
**Sec. 34, T. 19S, R. 23E.**  
**Grand County, Utah**

**Well No. Bowers State 2-36**  
**Sec. 36, T. 19S, R. 23E.**  
**Grand County, Utah**

Gentlemen:

Our records indicate that you have not filed a Subsequent Report of Abandonment for the above subject wells.

Rule D-2, General Rules and Regulations and Rules of Practice and Procedure, requires that said reports be filed within thirty (30) days after the plugging of any well.

In order that we may keep our records accurate and complete, please complete the enclosed Form OGC-1B, and forward them to this office as soon as possible.

Your prompt attention to the above will be greatly appreciated.

Very truly yours,

DIVISION OF OIL, GAS, & MINING

JANICE TABISH  
CLERK-TYPIST

BOWERS OIL & GAS EXPLORATION INC.

P.O. Box 636

GRAND JUNCTION, CO. 81502

BUS: 303-245-1342

RES: 303-242-6311

June 5, 1980

Utah Oil & Gas Commission  
1588 W.N. Temple  
Salt Lake City, Utah 84116


Attention: Ms. Janice Tabish

RE: Bowers State Well #2-36 and  
Bowers Federal Well #1-34,  
both in Grand County, Utah.

Dear Ms. Tabish:

This letter is in reply to your letter to us dated June 3, 1980 in which you informed us Form OGC-1B should have been sent in on the above captioned wells. For your information, well #2-36 was plugged on June 3, 1980 and well #1-34 will be plugged today, June 6, 1980. All required paperwork on these wells will be sent in on time.

Sincerely,



James E. Bowers  
President

JEB:lam

RECEIVED  
JUN 12 1980

DIVISION OF  
OIL, GAS & MINING

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEYSUBMIT IN TRIPLICATE\*  
(Other instructions on re-  
verse side)Form approved.  
Budget Bureau No. 42-R1424.

5. LEASE DESIGNATION AND SERIAL NO.

71-14267

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

n/a

7. UNIT AGREEMENT NAME

n/a

8. FARM OR LEASE NAME

n/a

9. WELL NO.

Bowers Fed. Well #1-34

10. FIELD AND POOL, OR WILDCAT

Unnamed

11. SEC., T., R., M., OR BLK. AND  
SURVEY OR AREASec. 34, T19S, R23E,  
S1B & M

12. COUNTY OR PARISH

Grand

13. STATE

Utah

## SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)1. OIL ☐ GAS ☒ WELL ☒ OTHER

2. NAME OF OPERATOR

Bowers Oil &amp; Gas Expl., Inc.

3. ADDRESS OF OPERATOR

P.O. Box 636, Grand Junction, CO 81502

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.\*  
See also space 17 below.)  
At surface1780 ft. FEL  
1120 ft. FSL

14. PERMIT NO.

43-019-30573

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

4967 ft. (KB)

## 10. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

## NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐(Other) ☐PULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐ABANDON\* ☐CHANGE PLANS ☐

## SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☐(Other) ☐REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT\* ☒(NOTE: Report results of multiple completion on Well  
Completion or Recompletion Report and Log form.)17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any  
proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones perti-  
nent to this work.)\*

We finished plugging and abandoning this well 6/10/80. Plugging operation went as follows (all footage KB): (1) Hole was filled with 9ppg. mud; (2) Plug #1 (2305' - 2515'), 20 SKS Class B cement; Plug #2 (981' - 1181'), 20 SKS Class B cement; (3) Plug #3 (85' - 250'), 12 SKS Class B cement; (4) Plug #4 (surface plug), 25 SKS Class B cement w/regulation marker.

Location has been cleaned up, the pit backfilled, and the topsoil contoured back to its original position. Reseeding will take place this fall.

RECEIVED  
JUL 10 1980  
DIVISION OF  
OIL, GAS & MINING

18. I hereby certify that the foregoing is true and correct

SIGNED

*James H. Bowers*

TITLE

President

DATE 7/12/80

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

\*See Instructions on Reverse Side